



MIDWAY
SEALCOATING & STRIPING CO

P.O. Box 180953 Arlington, TX 76096

817-467-7003/F817-465-1665

www.midwaysealcoating.com

Proposal

August 8, 2015

Quail Creek HOA
314 Partridge
Rockwall, TX
David Fuller
Df61@sbcglobal.net

Concrete Repairs: 1,250 sq. ft.

Sawcut and Remove proposed area. Haul off debris from jobsite. Form proposed area. Place cushion sand level up as needed. Place 5" 3,000 PSI Concrete using #3 (3/8") Rebar O.C.E.W. (on center each way). Allow concrete to cure and apply broom finish. Allow finished concrete to cure and sawcut control joint 15" o.c. or as needed. This is to be done in two phases to allow entry and exit into sub division.

\$15,000.00

By signing this document, both parties acknowledge to have read, understand & agree to the above.
I have read and agree with the terms and conditions of this contract.

Signed

Lawrence O'Leary

Accepted

Robert Steinhagen

Date 8/5/2015

Print Name

ROBERT STEINHAGEN

Title

PRESIDENT, QUAIL CREEK HOA